SIMPLY RELIABLE



ESYDOX MAX

CONNECTED, EFFICIENT, MODULAR.



ESYBOX MAX MODULAR WATER PRESSURE **BOOSTER PUMP**

CREATE YOUR BOOSTER MODULE SOLUTION OF UP TO FOUR PUMPS TO MEET DEMAND

The ESYBOX Max is a scalable booster pump solution for large homes, apartment buildings, hotels, light industrial use, hospitals, golf courses, and other applications where high pressure or high flow is needed.

APPLICATIONS

Esybox Max is the most compact and integrated booster set available compared with any traditional solution. It's not larger – it's modular.

Esybox Max is an integrated pumping system for water pressurization in commercial buildings. Available in two power sizes, it consists of modular elements that enable different configurations to meet the needs of medium to large condominiums and high-rise buildings up to 14 stories.

Each unit consists of single, double or triple connection base and the pumping units.

Now you only need to select from two different hydraulic models depending on the height of the building. Then you can create your booster set, with up to four pumps, to meet the demand.





Example: 6 floors 80 Rooms



100 Beds








ENERGY SAVINGS UPTO 20% COMPARED TO TRADITIONAL SOLUTIONS'

AS QUICK AS A "CLICK"

Install Esydock into your pipework system and simply "plug" your pumps in. A final quick set up





ESybox max



BUILT-IN CONNECTIVITY WITH H2D

EsyBox Max is compatible with DAB's H2D cloud service, giving you remote access to monitor and manage the pump anytime, from anywhere. View system status, adjust settings, and respond to issues faster—all from your phone or desktop.


H2D FREE FEATURES

- Check performance anytime
- Ensure optimal water pressure and flow
- Access comfort features like Power Shower and smarter usage timing

H2D PREMIUM FEATURES

- Remote configuration and control
- Real-time alerts for faster issue resolution
- Added confidence and convenience—fewer site visits, happier customers

Learn more: www.h2d.com













The modular OSA (On Site Assembly) feature allows for easy access to the installation area. This enables assembly on-site following our quick assembly steps.

ESY I/0

The expansion module (Esy I/O available accessory) makes it possible to interface Esybox Max with

external input/output devices (eg: float switch, pressure switch remote alarm) and with the BMS ecosystem (Building Management System).



CERTIFICATIONS





CONNECTED, EFFICIENT, MODULAR. CONSULT YOUR LOCAL DAB DISTRIBUTOR







MORE BENEFITS AND DETAILS:





DAB PUMPS USA 3226 Benchmark Drive Ladson, SC 29456 USA service.us@dabpumps.com

Tel: 1-843-797-5002 Fax: 1-843-797-3366